



FURUKAWA
ELECTRIC GROUP



VISCAS Corporation

Shigeru Fujii
(FURUKAWA ELECTRIC CO.,LTD.)

Hideo Tanaka
(VISCAS Corporation)

Sub C in 2013 Fall ICC Meeting

Power transmission system for "Fukushima FORWARD Project"

-- Power cable system
for offshore floating type wind farm pilot plant --



Project Location



Tsunami Damaged Area

March 11, 2011, extra large earthquake took place in East-North Japan and resulted extremely severe damage in that area as well as Fukushima #1 nuclear P/S.

Fukushima

Fukushima #1
Nuclear P/S

Project Area



Project Target

- Offshore floating wind farm project
 - ✓ Introduction of new renewable energy
 - ✓ Trial project of total system verification
 - ✓ Potential availability of wind energy in Japanese EEZ
 - ✓ To help industrial revival of Tsunami-damaged regions in Fukushima Prefecture
- To be performed as consortium project financed by Japanese government



Project formation

Fukushima Offshore Wind Farm Consortium

Project Integrator

Japanese Leading Companies

Engineering

Wind Turbine

Floating System

Marine Construction

Advanced Steel Material

Substation

Power Transmission

.....


[Riser and Submarine Cable] Development and Installation

Our company F

Technical
advisor

Subcontract


Our company V





Project Outline (1)

Off shore facilities --- Final system



Source :Fukushima Offshore Wind Farm Consortium



Project Outline (2)

1st Stage 2011–2013

2nd Stage 2014–2015

25MVA
Floating S/S



2MW Turbine



7MW Turbine-1




7MW Turbine-2



Source :Fukushima Offshore Wind Farm Consortium



Power Transmission System 1st stage outline





Development of Riser Cable

Cigre TB-490

JEC-3408

Cigre Electra No.171

+

Target characteristics.

Item	Target characteristics
Sea condition at installation site	• Meet allowable tension and minimum bending radius in floating condition
Floating structure rolling condition	• Floating part of the cable should not touch the sea bed • Cable should not be kinked
Fatigue life design	• Similar to windmill or floating structure

Wave conditions.

Item	Adoption value
The 50-year-period-return value associated with a storm wave	Significant wave height(note) 11.71 m
	Significant wave period 13 sec.
Sea current	1.5 m/s (including drift current)

(Note) The average wave height is defined as the average values from the highest record and the consecutive values of 1/3 measurements of the total measurements recorded of the period of recording (for example 20 min) at a certain point.

Static behavior analysis

Dynamic behavior analysis

Fatigue analysis

Riser Cable Design

OK



Outline Spec. of Riser Cables

	Unit	66kV	22kV
Outer Diameter of Cable	mm	175	150
Cable Weight	kg/m (in air)	53	43
Moisture/Water barrier	----	Corrugated Stainless Steel Sheath	Stainless Steel Foil Laminated Tape
Optical Fiber Unit	----	8 fibers x 3 unit	8 fibers x 1 unit
Steel Armor	----	Two Layers	




Important Aspects of Riser Cable System Development

- **22kV Riser Cable**
 - Moisture/Water barrier structure and its properties
 - Mechanical properties for dynamic movements
- **66kV Riser Cable**
 - Mechanical properties for dynamic movements
- **Transition Joint (66kV Riser to Submarine)**
 - Water pressure resistance
 - Tensile strength on conductor joint sleeve as well as whole structure




Design Flow of Riser Cable (1)




*FS: Floating Structure

Cable profile in water






Design Flow of Riser Cable (2)



Design of 66kV Riser Cable

Water Blocking Structure with Corrugated Stainless Steel Sheath



Conductor	3 x 100 mm ²
XLPE Insulation	11 mm
Inner PE jacket	3.5 mm
Armour	Galvanized steel wire (6.0 mm)
Outer PE jacket	6 mm
Outer diameter	175 mm
Weight	53 kg/m in air

Installed cable length: 860m




66kV Riser Cable



66kV Riser Cable

22kV Riser Cable

Water Blocking Structure with Stainless Steel Foil Laminated Tape



Installed cable length: 2340m

Conductor	3 x 150 mm ²
XLPE Insulation	6 mm
Metallic sheath	Stainless steel foil laminated tape(0.6mm)
Inner PE jacket	3.5 mm
Armour	Galvanized steel wire (6.0 mm)
Outer PE jacket	6 mm
Outer diameter	147 mm
Weight	43 kg/m in air




22kV Riser Cable




22kV Riser Cable

Design of 66kV transition joint between riser and submarine cable



Water Pressure Resistance	1.5MPa OK
Tensile Strength on Conductor Joint Sleeve	> 7kN



Rigid joint worked on the laying vessel




66kV transition joint between riser and submarine cable



66kV transition joint on the laying vessel

Design of 66kV submarine cable



Conductor	3 x 100 mm ²
XLPE Insulation	11 mm
Metallic sheath	Extruded lead alloy (2 mm)
Armour	Galvanized steel wire (6.0 mm)
Outer diameter	123 mm
Weight	32 kg/m in air

66kV submarine cable



66kV submarine cable



Project Schedule

1st stage project completed

- Cable production:
~2013 Summer
- Riser cable installation:
~2013 August-September
- System commissioning:
2013 October
- **1st stage project in operation:**
2013 November~



Riser Cables Installation (1)



Laying vessel



66kV riser laying at S/S



Bend stiffner



Chinese finger



Cable turn table



ROV



Riser Cables Installation (2)



2MW Wind turbine



22kV riser laying at S/S



Floating S/S




22kV riser laying at turbine



22kV riser below turbine




Riser Cables Installation (3)



Transition joint on the vessel



Joint laying



Joint is going into sea



Joint on the sea bed



Riser Cables Installation (4)

➤ On-site test for final Inspection

66kV cables	DC 151.8kV x 10min. Passed
22kV cables	DC 57.5kV x 10min. Passed




On-site test for 22kV Cable



On-site test for 66kV Cable

2nd Stage Project Outline



Floating S/S




2MW Turbine



7MW Turbine-1



7MW Turbine-2



66kV Riser Cable

Transition joint

66kV Submarine Cable

22kV Riser Cable

22kV Riser Cable

1st Stage

2nd Stage



2nd Stage Project Schedule

	2013	2014			2015		
Cable Manufacturing		[Orange bar spanning Q1-Q2 2014]			[Orange bar spanning Q1-Q2 2015]		
Cable Installation		[Orange bar spanning Q2-Q3 2014]			[Orange bar spanning Q2-Q3 2015]		
Cable Joint on site			[Orange bar in Q3 2014]			[Orange bar in Q3 2015]	
Final Inspection						[Orange bar in Q3 2015]	



Thank you for your attention!

References: [1] Fujii, et. al.; "The Development of the Power Transmission System for Fukushima FORWARD Project", Furukawa Review 43, (March 2013)
[2] Fukushima Offshore Wind Farm Consortium, Brochure on Fukushima FORWARD Project

This research is carried out as a part of Fukushima floating offshore wind farm demonstration project funded by the Ministry of Economy, Trade and Industry.

The authors wish to express their deepest gratitude to the concerned parties for their assistance during this study. 28